

NORWALK RIVER BASIN  
GEORGETOWN CONNECTICUT

# FACTORY POND DAM CT 00217

## PHASE I INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM



The original hardcopy version of this report  
contains color photographs and/or drawings.  
For additional information on this report  
please email

U.S. Army Corps of Engineers  
New England District  
Email: [Library@nae02.usace.army.mil](mailto:Library@nae02.usace.army.mil)

DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

JULY 1980

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CT 00217	2. GOVT ACCESSION NO. ADA14359	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Factory Pond Dam  NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE July 1980
		13. NUMBER OF PAGES 60
		15. SECURITY CLASS. (of this report)  UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY,  Norwalk River Basin Georgetown Conn. Factory Pond Dam		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Factory Pond Dam is a combination of sheet piling/concrete fill and masonry that is approx. 175 ft. long and 18.75 ft. high. The sheet piling portion of the dam consists of two rows of piling, 5 ft. apart, filled with concrete. The assessment of the dam is based on the visual inspection, past operational performance and hydraulic/hydrologic computations. The dam is judged to be in fair condition with several areas that require attention. The dam is classified as small and has a high hazard potential in accordance with guidelines established by the Corps of Engineers.		

FACTORY POND DAM

CT 00217

NORWALK RIVER BASIN

GEORGETOWN, CONNECTICUT

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM

## NATIONAL DAM INSPECTION PROGRAM

### PHASE I INSPECTION REPORT

Identification Number:	CT 00217
Name:	Factory Pond Dam
Town:	Redding
County and State:	Fairfield County, Connecticut
Stream:	Norwalk River
Date of Inspection:	April 23, 1980

### BRIEF ASSESSMENT

Factory Pond Dam is a combination of sheet piling/concrete fill and masonry that is approximately 175 feet long and 18.75 feet high. The sheet piling portion of the dam consists of two rows of piling, 5 feet apart, filled with concrete. The spillway is located on the southern portion of the dam and consists of a 75-foot long masonry weir. There is a 5-foot diameter discharge pipe that passes through the dam and an adjacent factory. Inside this pipe is a turbine that was once used for water power, but is now only used as a valve. The drainage area is 12.2 square miles and the reservoir has 92 acre-feet of available storage.

The assessment of the dam is based on the visual inspection, past operational performance and hydraulic/hydrologic computations. The dam is judged to be in fair condition with several areas that require attention. These areas include seepage in the vicinity of the west abutment of the spillway, concrete that needs repairing and masonry that needs repointing.


The dam is classified as small and has a high hazard potential in accordance with guidelines established by the Corps of Engineers. The test flood for this dam is 1/2 the Probable Maximum Flood (PMF). The test flood inflow is 9,640 cfs and the routed test flood outflow is 8,250 cfs. The test flood will overtop the dam by 4.25 feet.



It is recommended that the owner engage the services of a qualified registered engineer experienced in the design of dams to investigate the seepage through the dam and prepare a detailed hydraulic/hydrologic study to determine the spillway's adequacy.

Additional recommendations and remedial measures are included in Section 7 and should be implemented within one year after receipt of this Phase I Inspection Report.

  
Joseph F. Merluzzo  
Connecticut P.E. #7639  
Project Manager

  
Gary J. Giroux  
Connecticut P.E. #11477  
Project Engineer

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Inspections. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Inspection is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Inspection; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I Inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the Spillway Test Flood is based on the estimated Probable Maximum Flood for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and variety of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Inspection does not include an assessment of the need for fences, gates, "no trespassing" signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with Occupational Safety and Hazard Administration's (OSHA) rules and regulations is also excluded.

## TABLE OF CONTENTS

	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface . . . . .	i
Table of Contents . . . . .	ii-iv
Overview Photo	
Location Map	

### Section

#### 1. PROJECT INFORMATION

1.1 General . . . . .	1
a. Authority . . . . .	1
b. Purpose of Inspection . . . . .	1
1.2 Description of Project . . . . .	1
a. Location . . . . .	1
b. Description of Dam and Appurtenances . . . . .	2
c. Size Classification . . . . .	2
d. Hazard Classification . . . . .	2
e. Ownership . . . . .	3
f. Operator . . . . .	3
g. Purpose of Dam . . . . .	3
h. Design and Construction History . . . . .	3
i. Normal Operational Procedure . . . . .	3
1.3 Pertinent Data . . . . .	3

#### 2. ENGINEERING DATA

2.1 Design Data . . . . .	8
2.2 Construction Data . . . . .	8
2.3 Operation Data . . . . .	8
2.4 Evaluation of Data . . . . .	8

#### 3. VISUAL INSPECTION

3.1 Findings . . . . .	9
a. General . . . . .	9
b. Dam . . . . .	9
c. Appurtenant Structures . . . . .	9
d. Reservoir Area . . . . .	10
e. Downstream Channel . . . . .	10

<u>Section</u>	<u>Page</u>
3.2 Evaluation . . . . .	10
4. OPERATIONAL AND MAINTENANCE PROCEDURES	
4.1 Operational Procedures . . . . .	11
a. General . . . . .	11
b. Description of any Warning System in Effect . .	11
4.2 Maintenance Procedures . . . . .	11
a. General . . . . .	11
b. Operating Facilities . . . . .	11
4.3 Evaluation . . . . .	11
5. EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES	
5.1 General . . . . .	12
5.2 Design Data . . . . .	12
5.3 Experience Data . . . . .	12
5.4 Test Flood Analysis . . . . .	13
5.5 Dam Failure Analysis . . . . .	13
6. EVALUATION OF STRUCTURAL STABILITY	
6.1 Visual Observations. . . . .	15
6.2 Design and Construction Data . . . . .	15
6.3 Post-Construction Changes . . . . .	15
6.4 Seismic Stability . . . . .	15
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	
7.1 Dam Assessment . . . . .	16
a. Condition . . . . .	16
b. Adequacy of Information . . . . .	16
c. Urgency . . . . .	16
7.2 Recommendations . . . . .	16

<u>Section</u>	<u>Page</u>
7.3 Remedial Measures . . . . .	16
a. Operation and Maintenance Procedures . . .	16
7.4 Alternatives . . . . .	17

#### APPENDICES

APPENDIX A - Inspection Checklist

APPENDIX B - Engineering Data

APPENDIX C - Photographs

APPENDIX D - Hydrologic and Hydraulic Computations


APPENDIX E - Information as Contained in the National  
Inventory of Dams






FACTORY POND DAM





QUADRANGLE: **BETHEL, CT**

**US ARMY, CORPS OF ENGINEERS**  
**NEW ENGLAND DIVISION**  
**WALTHAM, MASS.**



**LOCATION MAP**

PHASE I INSPECTION REPORT  
FACTORY POND DAM CT 00271

SECTION 1 - PROJECT INFORMATION

1.1 General

a. Authority - Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspections throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Storch Engineers has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed were issued to Storch Engineers under a letter of March 6, 1980 from William E. Hodgson, Jr., Colonel, Corps of Engineers. Contract No. DACW33-80-C-0035 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection -

(1) Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) Encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location - Factory Pond Dam is located approximately 1,200 feet north of the Route 57 and Route 107 interchange and east of Route 7 in the Georgetown



section of the Town of Redding, Connecticut (See Location Map). The coordinates of the dam are approximately 41°-15.5' north latitude and 73°-26' west longitude. The dam is located on the Norwalk River in the Norwalk River Basin.

b. Description of Dam and Appurtenances - Factory Pond Dam is a combination of sheet piling/concrete fill and masonry that is 175 feet long and 18.75 feet high. The sheet piling portion of the dam consists of two rows of sheet piling spaced 5 feet apart, with concrete fill in between. The sheet piling extends to 20 feet below the top of the dam.

The spillway is a stone masonry weir with an ogee section that is 75 feet long. The top of the dam is 4.65 feet above the spillway crest. The spillway is located on the southern portion of the dam adjacent to a factory building. There is a 10-foot downstream apron with the remainder of the channel being riprap.

There is a 5-foot diameter discharge conduit that is used to lower the pond for repairs to the dam. This conduit has a variable pitch blade turbine in it that was once used for water power. Presently, the turbine is not used for power but the blades are used as a control valve. Control of the blades is from inside the factory.

c. Size Classification - Factory Pond Dam has a maximum height of 18.75 feet and a maximum storage of 192 acre-feet at the top of the dam. In accordance with the Recommended Guidelines for Safety Inspection of Dams established by the Corps of Engineers, the dam is classified as intermediate (height less than 40 feet and storage less than 1,000 acre-feet).

d. Hazard Classification - Factory Pond Dam is classified as having a high hazard potential. Failure of the dam could result in the loss of more than a few lives and cause significant property damage. Approximately 50 feet

downstream is a Gilbert & Bennett manufacturing building built immediately over the river. Estimated flow and water depths just prior to dam failure at this location is 2,500 cfs at 8.5 feet and just after dam failure is 5,710 cfs at 22 feet.

- e. Ownership - The Factory Pond Dam is owned by:

Gilbert & Bennett  
Georgetown, Connecticut

- f. Operator - The person in charge of day-to-day operation of the dam is:

Mr. Dom Curtis  
Gilbert & Bennett  
Georgetown, Connecticut  
(203) 544-8323

- g. Purpose of Dam - The dam impounds the Factory Pond which serves as a primary water supply for industrial use by Gilbert & Bennett.

h. Design and Construction History - There are no design computations or drawings available for the original dam. During the Flood of "55", the dam was damaged as a result of water flowing through a low spot in the area of the west abutment. The water never overtopped the dam. The dam was reconstructed in 1956. Drawings are available for this reconstruction. Essentially, this reconstruction was of the western abutment, which is now sheet piling/concrete fill. The design was done by Industrial Associates, Inc., Philadelphia, Pennsylvania. In 1968, the masonry face was gunited.

- i. Normal Operational Procedure - There is a regular maintenance staff at the plant that takes care of the dam. The water level of the pond is lowered if a major storm is imminent.

### 1.3 Pertinent Data

- a. Drainage Area - Factory Pond drainage basin is in the Towns of Ridgefield, Redding, Wilton and Weston and is irregular in shape. The area of

the drainage basin is 12.2 square miles (Appendix D - Plate 3). Approximately 10 percent of the drainage basin is natural storage and more than 80 percent is undeveloped. The topography is rolling with elevations ranging from 840 (NGVD) to 329 (NGVD) at the spillway crest.

b. Discharge at Damsite - There are no records available for discharge at the dam.

(1) Outlet works (conduit) size:	60 inches
Invert elevation (feet above NGVD):	319
Discharge Capacity at top of dam:	40 cfs
(2) Maximum known flood at damsite:	4,800 cfs
(3) Ungated spillway capacity at top of dam:	2,500 cfs
Elevation (NGVD):	333.65
(4) Ungated spillway capacity at test flood elevation:	6,700 cfs
Elevation (NGVD):	337.9
(5) Gated spillway capacity at normal pool elevation:	N/A
Elevation (NGVD):	N/A
(6) Gated spillway capacity at test flood elevation:	N/A
Elevation:	N/A
(7) Total spillway capacity at test flood elevation:	6,700 cfs
Elevation	337.9
(8) Total project discharge at top of dam:	2,540 cfs
Elevation (NGVD):	333.65

(9) Total project discharge at test flood	
elevation:	8,250 cfs
Elevation (NGVD):	337.9
c. Elevation (feet above NGVD)	
(1) Streambed at toe of dam:	314.9
(2) Bottom of cutoff:	313.65
(3) Maximum tailwater:	323.4
(4) Normal pool:	329
(5) Full flood control pool:	N/A
(6) Spillway crest (ungated):	329
(7) Design surcharge (original design):	unknown
(8) Top of dam:	333.65
(9) Test flood surcharge:	337.9
d. Reservoir (length in feet)	
(1) Normal pool:	1,700
(2) Flood control pool:	N/A
(3) Spillway crest pool:	1,700
(4) Top of dam:	1,800
(5) Test flood pool:	2,000
e. Storage (acre-feet)	
(1) Normal pool:	100
(2) Flood control pool:	N/A
(3) Spillway crest pool:	100
(4) Top of dam:	192
(5) Test flood pool:	282
f. Reservoir Surface (acres)	
(1) Normal pool:	16.5

	(2) Flood control pool:	N/A
	(3) Spillway crest:	16.5
	(4) Test flood pool:	23
	(5) Top of dam:	20
g.	Dam	
	(1) Type:	sheet piling/concrete fill & stone masonry
	(2) Length:	175
	(3) Height:	18.75
	(4) Top width:	5 feet
	(5) Side slopes:	vertical
	(6) Zoning:	unknown
	(7) Impervious core:	N/A
	(8) Cutoff:	sheet piling down to elevation 313.65 (NGVD)
	(9) Grout curtain:	unknown
	(10) Other:	N/A
h.	Diversion and Regulating Tunnel	N/A
i.	Spillway	
	(1) Type:	stone masonry weir/ogee
	(2) Length of weir:	75 feet
	(3) Crest elevation (without flashboard):	329
	(4) Gates:	N/A
	(5) U/S channel:	no channel-natural pond bottom
	(6) D/S channel:	concrete apron and riprapped channel

(7) General:	N/A
j. Regulating Outlets	
(1) Invert elevation (NGVD):	319
(2) Size:	60 inches
(3) Description:	cast iron pipe
(4) Control Mechanism	manually operated gate
(5) Other:	valve is the variable pitch blades of the turbine

## SECTION 2 - ENGINEERING DATA

### 2.1 Design Data

There are no design computations or drawings for the original dam. However, there are drawings for the reconstructed portion of the dam that was damaged during the Flood of October, 1955. These drawings were prepared by Industrial Associates, Inc. of Philadelphia, Pennsylvania (See Appendix B).

### 2.2 Construction Data

No records are available for the original construction or the reconstruction. Drawings for the reconstruction are available (Appendix B).

### 2.3 Operation Data

The gate for the 5-foot diameter discharge conduit is operable and it is exercised periodically to lower the pond. Also, when the threat of a major storm is imminent, the pond is lowered.

### 2.4 Evaluation of Data

a. Availability - There were no computations available, however, there are some drawings available. These drawings are available from the Department of Environmental Protection (DEP).

b. Adequacy - The information made available along with the visual inspection, past performance history and hydraulic/hydrologic assumptions were adequate to assess the condition of the facility.

c. Validity - Due to the lack of available data, the conclusions and recommendations found in this report are based on the visual inspection and hydraulic/hydrologic computations.

## SECTION 3 - VISUAL INSPECTION

### 3.1 Findings

a. General - The visual inspection was conducted on April 23, 1980 by members of the engineering staff of Storch Engineers, D. Baugh and Associates, Inc. and Matthews Associates with the help of Mr. Peter Harco and Dom Curtis of Gilbert & Bennett. A copy of the visual inspection check list is contained in Appendix A of this report. Selected photos of the dam and appurtenant structures are contained in Appendix C.

In general, the overall appearance and condition of the facility and its appurtenant structures is fair.

b. Dam - The dam is a combination of sheet piling/concrete fill and masonry. The sheet piling and concrete fill are in good condition (Photo 1). The sheet piling is painted with some areas that are rusting. The concrete cap is in good condition with no cracking (Photo 3). There is no evidence of settlement or lateral movement. There are some areas along the toe where vegetation is growing (Photo 1). The masonry portion of the dam is fair with some joints in need of repointing (Photo 8).

c. Appurtenant Structures - The inlet to the discharge conduit is protected by a bar screen which is in good condition. The discharge conduit itself was underwater and could not be inspected (Photo 8). The conduit contains a power turbine which is not used. The control for this conduit is by varying the pitch on the blades of the turbine. The gate is operable and the conduit was in use at the time of inspection.



The spillway is a fixed weir that appears to be in fair condition (Photos 2 and 5). The downstream training wall and western abutment (Photos 1 and 6) show some seepage and cracks.

d. Reservoir Area - The area immediately adjacent to the facility is gently sloped and in a natural state. The shoreline shows no signs of sloughing or erosion. There is some development adjacent to the reservoir, which is in the form of warehouses owned by Gilbert & Bennett. A rapid rise in the water level of the reservoir will not endanger any life or property.

e. Downstream Channel - The channel from the spillway is confined by buildings and many bridges (Photos 3, 4 and 7). It is a stone lined, but its capacity is questionable. Immediately downstream, the channel passes under a building (Photo 4). Under a large flow, the pier shown in the picture and the building may be destroyed.

### 3.2 Evaluation

Overall, the general condition of the dam is fair. The visual inspection revealed items that lead to this assessment, and apparent areas of distress such as:

- a. Seepage through the abutment.
- b. Need for repointing of the masonry.
- c. Vegetation along the toe of the dam.

## SECTION 4 - OPERATIONAL AND MAINTENANCE PROCEDURES

### 4.1 Operational Procedures

a. General - The operation of this facility is strictly for the purpose of industrial use, and the water level is kept as full as possible. Water for industrial use is pumped out. The pond is lowered once a year when manufacturing operations are shut down.

b. Description of Any Warning System in Effect - The only formal operating procedure is when there is a threat of a substantial storm. When this occurs, the gate to the 5-foot diameter conduit is opened and the water level in the pond is lowered (5 feet in 24 hours). There is no system for warning downstream inhabitants.

### 4.2 Maintenance Procedures

a. General - The pond is drained each year during the manufacturing shut down. At this time, the mortar is repaired and the cracks are filled.

b. Operating Facilities - The gate to the 5-foot discharge conduit was taken apart and refurbished approximately ten years ago.

### 4.3 Evaluation

The dam is maintained on an annual basis. Although they do lower the pond prior to a major storm, there should be a formal warning system for downstream flooding.

## SECTION 5 - EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

### 5.1 General

Factory Pond Dam is a sheet piling/concrete fill and masonry dam approximately 175 feet long and 18.75 feet high. The spillway is a masonry weir, 75 feet long. The 5-foot diameter conduit is used to lower the pond before a major storm and according to maintenance personnel, it takes 24 hours to lower the pond 5 feet ( $14.2 \text{ acres} \times 5.0 \text{ feet} \div 24 \text{ hours} = 35.8 \text{ cfs}$ ). Compared to the test flood, this flow is small. Therefore, this conduit is not in the hydrologic analysis.

The watershed encompasses 12.2 square miles and is 80 percent undeveloped. The topography is rolling with the terrain rising 511 feet from the spillway crest.

The pond has a total capacity of 192 acre-feet when the pond is at the top of the embankment and 100 acre-feet at the spillway crest. Therefore, there is approximately 92 acre-feet of storage available. The test flood outflow for this dam is 8,250 cfs and the spillway capacity is 2,500 cfs or approximately 30% of the test flood outflow.

### 5.2 Design Data

No design data is available.

### 5.3 Experience Data

Factory Pond Dam has experienced all the major storms of the 1930's and 1950's and most recently January, 1979. The flood of record resulted from the storm of October, 1955. The discharge at the site was approximately 4,800 cfs and the western portion of the dam was damaged, resulting in its reconstruction.

#### 5.4 Test Flood Analysis

Based on the guidelines found in the Recommended Guidelines for Safety Inspection of Dams, the dam is classified as a small structure with a high hazard potential. The test flood for these conditions ranges from 1/2 the Probable Maximum Flood (PMF) to the PMF. One half the PMF was used for this dam because of the small size.

Using the guide curves established by the Corps of Engineers (rolling terrain), the test flood inflow is 9,640 cfs. The routing procedure established by the Corps gives an approximate outflow of 8,250 cfs. The spillway capacity is approximately 2,500 cfs or approximately 30% of the test flood outflow. The test flood will overtop the dam by approximately 4.3 feet. The building over the spillway (Photos 1 and 2) will not affect the test flood outflow.

Storage behind the dam was assumed to begin at the spillway crest. Storage was determined by an average area depth analysis. Capacity curves for the spillway assumed weir flow.

#### 5.5 Dam Failure Analysis

A dam failure analysis was performed using the Rule of Thumb method in accordance with guidelines established by the Corps of Engineers. Failure was assumed to occur when the water level in the reservoir was at the top of the dam.

The spillway discharge just prior to dam failure is 2,500 cfs and will produce a depth of flow of approximately 8.5 feet immediately downstream (at Gilbert & Bennett's building over the channel) from the dam. The calculated dam failure discharge is 5,710 cfs and will produce a depth of flow of approximately 22 feet immediately downstream from the dam or an increase in water

depth at failure of approximately 13.5 feet. The failure analysis covered a distance of approximately 1,000 feet downstream where the depth of flow was calculated to be 4.5 feet.

Failure of Factory Pond Dam may result in the loss of more than a few lives and the flood wave will destroy portions of the Gilbert & Bennett Factory which was constructed over the river 50 feet downstream. Also at least two dwellings located approximately 1,500 feet downstream will sustain some damage.

## SECTION 6 - EVALUATION OF STRUCTURAL STABILITY

### 6.1 Visual Observations

The general structural stability of the dam is good as evidenced by the vertical, horizontal and lateral alignment. The mortared stone spillway is in fair condition with some cracks in the concrete at the westerly end. The steel sheet piling is in good condition.

The only area of concern is at the western abutment/training wall where there is some cracking and some seepage. This seepage, at the time of inspection, was negligible.

### 6.2 Design and Construction Data

The original design and construction data are not available. There are construction drawings available for the reconstruction of the dam.

### 6.3 Post-Construction Changes

Since the reconstruction of the dam, the only changes, except for minor maintenance work, are the guniting of the stone masonry face of the spillway in 1968 and the addition of the covered passageway over the dam (Appendix B - Plate 1). One of the piers for this passageway was constructed across the outlet channel. This outlet channel has since ceased to function.

### 6.4 Seismic Stability

The dam is located in Seismic Zone 1 and in accordance with Recommended Phase I Guidelines does not warrant a seismic analysis.

## SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

### 7.1 Dam Assessment

a. Condition - After consideration of the available information, the results of the inspection, contact with the owner and hydraulic/hydrologic computations, the general condition of the Factory Pond Dam is fair.

b. Adequacy of Information - The information available is such that an assessment of the safety of the dam should be based on the available data, the visual inspection results, past operational performance of the dam and its appurtenant structures and computations developed for this report.

c. Urgency - It is considered that the recommendations suggested below be implemented within one year after receipt of this Phase I Inspection Report.

### 7.2 Recommendations

The following recommendations should be carried out under the direction of a qualified registered engineer.

- a. Seepage through the spillway abutment should be investigated further to determine its origin and monitored to determine any changes.
- b. Prepare a detailed hydraulic/hydrologic study to determine spillway adequacy and an increase of the total project discharge if necessary.

### 7.3 Remedial Measures

- a. Operation and Maintenance Procedures -

(1) Repair all cracks and mortar all joints in the masonry portion of the dam.

(2) Vegetation along the toe of the dam should be removed. This will facilitate the visual observation of existing and potential seepage.

(3) Plans for around-the-clock surveillance should be developed for periods of unusually heavy rains and a formal warning system should be put into operation for use in the event of an emergency.

(4) A program of annual technical inspection should be established.

#### 7.4 Alternatives

None.



Information pertaining to the history, maintenance and modification to  
Factory Pond Dam as well as copies of past reports are located at:

State of Connecticut  
Department of Environmental Protection  
Water Resources Unit  
State Office Building  
Hartford, Connecticut 06115

APPENDIX A

INSPECTION CHECK LIST

# INSPECTION CHECK LIST

## PARTY ORGANIZATION

PROJECT FACTORY POND DAM

DATE 4/23/80

TIME 9:00 a.m.

WEATHER Clear

W.S. ELEV. \_\_\_\_\_ U.S. \_\_\_\_\_ DN.S. \_\_\_\_\_

### PARTY:

- |   |   |
|---|---|
| 1. <u>John F. Schearer , SE Civil</u>     | 6. <u>Peter Haroo Gilbert &amp; Bennett</u> |
| 2. <u>John Pozzato , MA Mech.</u>         | 7. _____                                    |
| 3. <u>Kenneth J. Pudeler, SE Civil</u>    | 8. _____                                    |
| 4. <u>Michael Haire , DBA Struct/Geo.</u> | 9. _____                                    |
| 5. <u>Peter Austin , DBA Civil</u>        | 10. _____                                   |

### PROJECT FEATURE

### INSPECTED BY

### REMARKS

- |           |       |       |
|-----------|-------|-------|
| 1. _____  | _____ | _____ |
| 2. _____  | _____ | _____ |
| 3. _____  | _____ | _____ |
| 4. _____  | _____ | _____ |
| 5. _____  | _____ | _____ |
| 6. _____  | _____ | _____ |
| 7. _____  | _____ | _____ |
| 8. _____  | _____ | _____ |
| 9. _____  | _____ | _____ |
| 10. _____ | _____ | _____ |

# INSPECTION CHECK LIST

PROJECT FACTORY POND DAM

DATE 4/23/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

## AREA EVALUATED

## CONDITIONS

### DAM EMBANKMENT

Crest Elevation

Fair

Current Pool Elevation

Fair

Maximum Impoundment to Date

Never overtopped

Surface Cracks

Few (minor)

Pavement Condition

N/A

Movement or Settlement of Crest

None observed

Lateral Movement

Overall-good;

Vertical Alignment

Good

Horizontal Alignment

Good

Condition at Abutment and at Concrete Structures

Cracked joints noted in spillway side abutment

Indications of Movement of Structural Items on Slopes

None

Trespassing on Slopes

Not allowed

Vegetation on Slopes

None

Sloughing or Erosion of Slopes or Abutments

None

Rock Slope Protection - Riprap Failures

N/A

Unusual Movement or Cracking at or near Toes

None

Unusual Embankment or Downstream Seepage

Negligible

Piping or Boils

None

Foundation Drainage Features

None

Toe Drains

None

Instrumentation System

None

# INSPECTION CHECK LIST

PROJECT FACTORY POND DAM

DATE 4/23/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

## AREA EVALUATED

## CONDITION

### CUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE

#### a. Approach Channel

Slope Conditions

Good

Bottom Conditions

Good

Rock Slides or Falls

None

Log Boom

Good condition (spans pond)

Debris

Negligable (periodically cleaned out)

Condition of Concrete Lining

None observed

Drains or Weep Holes

None

#### b. Intake Structure

Condition of Concrete

Good

Stop Logs and Slots

Good

# INSPECTION CHECK LIST

PROJECT FACTORY POND DAM

DATE 4/23/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	N/A
a. Concrete and Structural	
General Condition	
Condition of Joints	
Spalling	
Visible Reinforcing	
Rusting or Staining of Concrete	
Any Seepage or Efflorescence	
Joint Alignment	
Unusual Seepage or Leaks in Gate Chamber	
Cracks	
Rusting or Corrosion of Steel	
b. Mechanical and Electrical	
Air Vents	None
Float Wells	None
Crane Hoist	None
Elevator	None
Hydraulic System	None
Service Gates	1-5' Penstock, Hand-operated worm gear - good condition.
Emergency Gates	Process water used by factory: valve pit & 10" hand valve - good condition
Lightning Protection System	None
Emergency Power System	None
Wiring and Lighting System in Gate Chamber	Within factory bldg., in good condition

# INSPECTION CHECK LIST

PROJECT FACTORY POND DAM

DATE 4/23/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u>	Inaccessable
General Condition of Concrete	"
Rust or Staining on Concrete	"
Spalling	"
Erosion or Cavitation	"
Cracking	"
Alignment of Monoliths	"
Alignment of Joints	"
Numbering of Monoliths	"

# INSPECTION CHECK LIST

PROJECT FACTORY POND DAM

DATE 4/23/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of <del>Concrete</del> <sup>Stone masonry</sup>	Fair
Rust or Staining	N/A
Spalling	None
Erosion or Cavitation	None
Visible Reinforcing	None
Any Seepage or Efflorescence	None
Condition at Joints	Fair
Drain holes	Fair
Channel	
Loose Rock or Trees Overhanging Channel	None
Condition of Discharge Channel	Good



# INSPECTION CHECK LIST

PROJECT FACTORY POND DAM DATE 4/23/80  
 PROJECT FEATURE \_\_\_\_\_ NAME \_\_\_\_\_  
 DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	
General Condition	Underwater
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	None
Floor of Approach Channel	Silted, otherwise good
b. Weir and Training Walls	
General Condition of Concrete	Good, but mortared joints on westerly training wall and abutting weir conc. cracked.
Rust or Staining	None
Spalling	None
Any Visible Reinforcing	None
Any Seepage or Efflorescence	Minor - westerly training wall/abutment
Drain Holes	None
c. Discharge Channel	
General Condition	Fair
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	None
Floor of Channel	Good
Other Obstructions	Several walkway bridges and buildings overhang the channel

# INSPECTION CHECK LIST

PROJECT FACTORY POND DAM

DATE 4/23/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - SERVICE BRIDGE</u></p> <p>a. Super Structure</p> <p>    Bearings</p> <p>    Anchor Bolts</p> <p>    Bridge Seat</p> <p>    Longitudinal Members</p> <p>    Under Side of Deck</p> <p>    Secondary Bracing</p> <p>    Deck</p> <p>    Drainage System</p> <p>    Railings</p> <p>    Expansion Joints</p> <p>    Paint</p> <p>b. Abutment &amp; Piers</p> <p>    General Condition of Concrete</p> <p>    Alignment of Abutment</p> <p>    Approach to Bridge</p> <p>    Condition of Seat &amp; Backwall</p>	<p>N/A</p>

## APPENDIX B

### ENGINEERING DATA

JOSEPH W. CONE  
CIVIL ENGINEER  
124 HAVEMEYER PLACE  
GREENWICH, CONNECTICUT

COMMISSION	
RECEIVED	
MAY 23 1963	
ANSWERED	_____
REFERRED	_____
FILED	_____

TELEPHONE  
TOWNSEND 9-2152

May 21, 1963

Mr. Emitt A. Dell, Field Inspector  
Water Resources Commission  
State Office Building  
Hartford 15, Conn.

Re: Dam #1 Norwalk River  
Gilbert & Bennett, Mfg. Co.

Dear Mr. Dell:

As requested, I inspected the above captioned dam on May 8, 1963. Many material changes have been made since I last saw the dam on August 13, 1957, when I read the weir gauge at the leak and estimated total flow at about 400,000 g.p.d. with FL in pond down about 6'. On May 8, '63 flow appeared to be greater than on August 13, '57 and I estimated flow at about 500,000 g.p.d., including small flows near west abutment of spillway. Flow at main leak shows in photo #2 enclosed.

More important reference correspondence

- (1) Dec. 23 '58 Cone to Wise
- (2) Jan. 9 '59 Mulliken to Wise
- (3) Feb. 1 '61 " " "
- (4) Feb. 8 '61 Cone " " re (3)

The material changes are shown very approximately on the enclosed photo of a topo sheet and not to scale.

Nos. 1 & 2 - New buildings

No. 3 - Channel widening and under old buildings.

Do not know increased area. But this has no particular relation with safety of dam.

Several piers are in channel for future building construction.

- No. 4 - Combined retaining and training wall; retaining to hold fill and presumably future building; training to direct flow lines from sluice gate.
- No. 5 - Drive through gate in fence from upper level El. 104.5 $\frac{1}{2}$ , datum spillway crest at 100.0, to lower level at building (2).
- No. 6 - Leaks in sluice gate chute and at west end of dam to be corrected.
- No. 7 - Suggest walls be raised as noted hereinafter.
- No. 8 - Entire area has been raised several feet above El. 104.5 by material excavated for new building at (2).
- No. 9 - Leaks at west end.

In addition: (a) Channel through grounds has been improved; (b) New bridge with greater waterway area at Route #465; (c) New twin box culvert added at new road Route #53.

Incidentally, I understand that new waterways at Route #465 and Route #53 will pass at least 2200 cfs with the usual clearance requirement of 2' between design flood water surface and underside of deck. The combination of

old and new box culverts at Route #53 under severe flood conditions can pass about 4000 cfs with H of 3' and Vm less than 10.

I would observe that design flood flow for passing floods through a valley is an entirely different matter than design flood flow for a dam; design for the one is influenced largely by the B-C ratio (benefit to cost); the design for a dam is imperatively concerned with safety. Leak. The leak at and near the sluiceway of about 500,000 g.p.d. could become a serious matter and cause failure of the westerly portion of the dam. Leaks must be controlled; therefore Recommendation No. 2.

A weir was installed in August 1957 to determine whether or not flow varied with changes in flow line of pond. The plant superintendent said he would have his plant carpenter note readings on the gauge and report to me. I instructed the carpenter how to measure from a mark on the gauge to water surface. No readings were furnished me. I did take one reading on Aug. 13, 1963.

Sheet Piling. Top of piling as shown on photo #1 averages over 1 foot below top of west masonry abutment and wall. I understand piles were 20' long and are tied to anchors and therefore are at minimum depth in original ground. Steel will deteriorate in about twenty years to

a condition requiring filling sluiceway with solid concrete to protect west end of main dam. Conditions must be checked periodically.

Conditions Now. Again referring to photo #1. This photo was taken from top of training wall at bend in same. The wall does not show in the left portion of the photo but it does reinforce toe of pavement to the extent that there is less likelihood of piling kicking out when dam is overtopped and scouring takes place. Also concrete, shown in photo to left of pipe, tends to reinforce paving.

To right of photo, but not shown, is the old projecting abutment wall. There are small leaks here and some stone in base moved. This area should be reinforced with massive concrete; therefore Recommendation No. 3.

Spillway. The old spillway could pass approximately 1100 cfs without serious overtopping. My estimate is that flood of October '55 was at least 4000 cfs at the dam. I was told there was only minor flow over east abutment in '53. Therefore the west end of dam must have failed at a flow of 1100 cfs or less or at less than one third of probable maximum flow.

Cone's letter (1) Dec. 23 '58 recommended among other matters --- "(3) Extend the overflow masonry dam to full width of the valley".

Mulliken's letter (3) Feb. 1 '61. "We recently developed a scheme to construct additional spillway capacity to the west of our present dam-----". And "As soon as a drawing has been completed, we will send you a copy for your preliminary study----". I have never seen such plan.

This extension of the spillway would have provided a total capacity of over 4200 cfs with present H of 4.6 and new length 130' effective ( $Q = 3.4 \times 130 \times 4.6^{3/2}$  (9.8) = 4230 cfs). And with H = 6 - 6500 cfs.

But the new building, walls, drives, etc. at #2 have most effectively checkmated this proposed solution which was practical and safe. Consequently I suggest raising all abutment walls to provide H = 7 as shown in recommendations.

As for the proposed diversion canal and conduits, this proposal is also blocked. However I always considered this a pipe-dream and not to be considered seriously.

It is my opinion that if additional spillway capacity is not provided the westerly portion of the dam will again fail due to overtopping and consequential scouring during a major flood.



I would remark that whatever Q was in October 1955 a future storm, in about 25 years, identical in every characteristic with 1955 storm would produce a much greater Q even up to 25%, because of:- (a) More intensive land use; (b) New bridges and culverts with greater waterway, thereby reducing valley storage; (c) Encroachment on and filling low areas, thereby again reducing valley storage; (d) Draining low areas.

I do not presently recommend an order to remove the dam once and for all, economic and other implications are evident.

I do recommend an order to make the corrections enumerated below or others of equivalent performance.

- (1) Owner furnish a map of conditions as they now are, showing in plan and elevations complete information. Particular reference to building (1) and old buildings and walls at (7). I have never seen a plan of this dam.
- (2) Effectively stop leaks at (9) west end of dam by grouting or otherwise.
- (3) When pipe at leaks has been completed and leaks stopped, place huge block of concrete between training wall and end of sluiceway and against bottom of spillway west abutment to reinforce same.

May 21, 1963

- (4) Raise walls at (7), to not less than El. 7.0 (west abutment and walls protecting old building) - this means raising about 2.5' minimum.
- (5) Uncover and measure upstream face of spillway to determine whether or not section is safe under extra H of 2.5'. If not safe reinforce front of dam with concrete.


Purpose of the above is to pass a reasonable design flood without washing out the westerly portion, as occurred in 1955, resulting in material damage not only to Gilbert and Bennett but to other properties and highway structures downstream.

Enclosed are two photographs, photo of general data notes and print of revised Recurrence Curve for Conn. Formula.

Yours very truly,

  
G. W. Cone

JWC/dr  
Enc: 2 photographs  
2 prints



## GEN. NOTES

5/20/63

Max Q without overtopping

Old Spilling 1050 cfs. with  $H = 2.7$ Present " 2250 " "  $H = 4.6$ 

'55 Flood. 3100 " on 8± sq. mi by USGS

" "  $\pm$  400± " per sq mi on 8 sq mi

Watershed 12.1 sq. mi at dam

'55 Flood 4800± cfs. (400x12) at dam Rough Q prob. some too high for dam.

Proposed Spilling 4000 cfs with  $H > 7$  minimum

MAF 850 cfs with CFS1 by Conc

Rough " check 810 " wtd. aver. of 8 steel sheds

$$\left. \begin{array}{l} \text{Min. Design} \\ H = 7 \end{array} \right\} R = \frac{Q}{MAF} = \frac{4000 \text{ cfs}}{800} = 5 \frac{1}{5} = 0.66\% \text{ chance (150 yr)}$$

$$'55 R \quad \frac{4800}{800} = 6 \frac{1}{5} = 0.5\% \text{ " (200 yr)}$$

Total precip.	12"	Danbury	at 14-17 in 155
"	9.6	Derby.	"
"	13.8	Stanford.	"

Procp of 9" Prob max in 24 hr on 12.5 sq. mi. and approx R is .7% (150 yr)

But prob nearly max runoff because of antecedent rain with swamps and brooks full.

1" per hr on 12.5 m 7,680 cfs if 100% runoff.

19.0


B-11

Accumulated Depth of Flood

Ratio Curve #1 as shown in Cont Flood Flow Formula (Gr 265 C5)

#2 as shown in Gr 1955 Leads  
#3 by Engineering - Thomas - Belmont

Chance Factor 4% 1% 1% 0.5% 0.2%



Recurrence Interval in Years J.W.C 12/18/56




PLATE 1


STORCH ENGINEERS  
WETHERSFIELD, CONNECTICUT

U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM MASS


NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

**FACTORY POND DAM**

SCALE: AS SHOWN  
DATE: JULY 1980



## SECTION A-A



## SECTION B-B

PLATE 2

STORCH ENGINEERS  
WETHERSFIELD, CONNECTICUT

U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CORPS. OF ENGINEERS  
WALTHAM MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

**FACTORY POND DAM**

NOT TO SCALE


SCALE: AS SHOWN

DATE: JULY 1980

APPENDIX C

PHOTOGRAPHS





NOT TO SCALE

# PHOTO LOCATION PLAN

PLATE 3

STORCH ENGINEERS  
WETHERSFIELD, CONNECTICUT

U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

## FACTORY POND DAM

SCALE: AS SHOWN

DATE JULY 1980





PHOTO 1  
DOWNSTREAM FACE OF DAM



PHOTO 2  
DOWNSTREAM FACE OF DAM





PHOTO 3  
DOWNSTREAM CHANNEL



PHOTO 4  
DOWNSTREAM CHANNEL





PHOTO 6

SEEPAGE THROUGH WEST SPILLWAY ABUTMENT



PHOTO 5

SPILLWAY CREST





PHOTO 7  
DOWNSTREAM CHANNEL



PHOTO 8  
SCREEN & DIVERSION INTAKE  
UPSTREAM FACE OF DAM  
C-IV

## APPENDIX D

### HYDROLOGIC AND HYDRAULIC COMPUTATIONS






PLATE 4

STORCH ENGINEERS  
WETHERSFIELD, CONNECTICUT

U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

# FACTORY POND DAM

scale 1:24000

SCALE AS SHOWN

DATE JULY 1980

Determination of Test Flood

NAME OF DAM Factory Pond Dam

DRAINAGE AREA 12.2 SM

INFLOW  $\frac{1}{2} \text{ PMF} = \frac{1}{2} (1580 \times 12.2) = 9638 \text{ cfs}$

Estimating the effect of surcharge storage on the Maximum Probable Discharges

1.  $Q_{P1} = 9640 \text{ cfs}$

2a.  $H_1 = 9.8' \text{ (elev.)}$

b.  $\text{STOR}_1 = 0.315''$

c.  $Q_{P2} = Q_{P1} (1 - \text{STOR}_1 / 19) = 9480 \text{ cfs}$

3a.  $H_2 = 9.6' \quad \text{STOR}_2 = 0.30$

b.  $\text{STOR}_A = 0.307$

$Q_{PA} = 9330 \text{ cfs}$

$H_A = 9.7''$

$\text{STOR}_A = 0.307$

Test Flood = 9330 cfs

Capacity of the spillway when the pond elevation is at the top of the dam

$Q = 2500 \text{ cfs or } 27\% \text{ of the Test Flood}$



**STORCH ENGINEERS**  
Engineers - Landscape Architects  
Planners - Environmental Consultants

JOB Phase I Dam Inspection 4463

SHEET NO. 2 OF 9


CALCULATED BY GJG DATE 4/16/80

CHECKED BY RDC DATE 7/15/80

**AREA - CAPACITY**

Name of Dam: FACTORY POND DAM

ELEV	DEPTH	AREA	AVG. AREA	VOL	Σ VOL
0.0		16.5			0.0
1.0	1.0	17.0	16.8	16.8	16.8
11.0	10.0	24.8	20.9	209	226



**STORCH ENGINEERS**  
Engineers - Landscape Architects  
Planners - Environmental Consultants

JOB: **Phase I Dam Inspection 4463**


SHEET NO. **3** OF **9**

CALCULATED BY **KJP** DATE **4/28/80**

CHECKED BY **BDC** DATE **7/15/80**

SCALE **Stage Discharge**

NAME OF DAM **FACTORY**



4/9

Project Factory Pond Dam


Designed By: RJG Date: 7/3/80

Town: Georgetown Route:

Checked By: BDC Date: 7/15/80

**HYDROLOGIC AND CHANNEL INFORMATION**

Downstream Culvert under Factory Floor




$Q_1 =$  \_\_\_\_\_  $TW_1 =$  \_\_\_\_\_  
 $Q_2 =$  \_\_\_\_\_  $TW_2 =$  \_\_\_\_\_

( $Q_1$  = DESIGN DISCHARGE, SAY  $Q_{25}$   
 $Q_2$  = CHECK DISCHARGE, SAY  $Q_{50}$  OR  $Q_{100}$ )

**SKETCH**

STATION: 50' distm from dam



MEAN STREAM VELOCITY = \_\_\_\_\_  
 MAX. STREAM VELOCITY = \_\_\_\_\_

CULVERT DESCRIPTION (ENTRANCE TYPE)	$\frac{1}{2}Q$	SIZE	HEADWATER COMPUTATION										CONTROLLING H	OUTLET VELOCITY	COST	COMMENTS
			INLET CONT		OUTLET CONTROL $HW = H + h_0 - LS_0$											
			$\frac{HW}{D}$	HW depth	$K_e$	H	$d_c$	$\frac{d_c + D}{2}$	TW	$h_0$	$LS_0$	HW depth				
	500	5' x 24'	.82	4.1	.5	4.5	2.3	3.7	3.7			3.65	4.1			
	1000		1.3	6.5		1.8	3.7	4.3	4.3			5.6	6.5			
	1500		2.1	10.5		4.0	4.8	4.9	4.9			8.4	10.5			
	2000		3.0	15.0		7.5	5.0	5.0	5.0			12.0	15.0			
	3000		6.0	30.0		16.3	5.0	5.0	5.0			20.5	30.0			


**SUMMARY & RECOMMENDATIONS**

D-5

**STORCH ENGINEERS**  
 Engineers - Landscape Architects  
 Planners - Environmental Consultants

JOB 41463  
 SHEET NO. 5 OF 9  
 CALCULATED BY GJG DATE 7/3/80  
 CHECKED BY BDC DATE 7/15/80  
 SCALE \_\_\_\_\_

Downstream Culvert Rating Curve  
 Depth (ft)



D-4

Downstream Hydrographs

**"Rule of Thumb" Guidance for Estimating Downstream Failure Hydrographs**

NAME OF DAM FACTORY

**Section I at Dam**

1.  $S = \frac{192}{8/27 W_b} \frac{\text{Acft}}{\sqrt{g}} Y^{3/2} = \frac{8}{27} (30) \sqrt{32.2} (23.4)^{3/2} = 5709 \text{ cfs}$
2.  $Q_{p1} = 8/27 W_b \sqrt{g} Y^{3/2} = 8/27 (30) \sqrt{32.2} (23.4)^{3/2} = 5709 \text{ cfs}$
3. See Sections

**Section II at**

- 4a.  $H_2 = 8.9'$   $A_2 = 225 \text{ ft}^2$   $L_2 = 800$   $V_2 = 4.1 \text{ Acft}$
  - b.  $Q_{p2} = Q_{p1} (1 - V_2/S) = 5587 \text{ cfs}$
  - c.  $H_2 = 8.9$   $A_2 = 225$   $V_2 = 4.1 \text{ Acft}$   
 $A_A = 225 \text{ ft}^2$
- $Q_{p2} = 5709 (1 - 4.1/192) = 5587$

**Section III at**

- 4a.  $H_3 = 7.0$   $A_3 = 275$   $L_3 = 1000$   $V_3 = 6.3 \text{ Acft}$
  - b.  $Q_{p3} = Q_{p2} (1 - V_3/S) = 5393 \text{ cfs}$
  - c.  $H_3 = 7.0$   $A_3 = 275$   $V_3 = 6.3 \text{ Acft}$   
 $A_A = 275$
- $Q_{p3} = 5587 (1 - 6.3/188) = 5400$

**Section IV at**

- 4a.  $H_4 = 7.0'$   $A_4 = 530$   $L_4 = 2100$   $V_4 = 26.0' \text{ Acft}$
  - b.  $Q_{p4} = Q_{p3} (1 - V_4/S) = 4630 \text{ cfs}$
  - c.  $H_4 = 6.5'$   $A_4 = 500$   $V_4 = 25.0' \text{ Acft}$   
 $A_A = 515$
- $Q_{p4} = 5400 (1 - 25/182) = 4660$

**STORCH ENGINEERS**  
Engineers - Landscape Architects  
Planners - Environmental Consultants

JOB 44/63  
SHEET NO. 6 OF 9  
CALCULATED BY KJP DATE 7/3/80  
CHECKED BY BDC DATE 5/15/80  
SCALE SECTION 1L

15T 800'

Building


Building

$n = .035$   
 $s = 2\%$

25'

100'

D	WP	A	R	R <sup>7/3</sup>	S <sup>1/2</sup>	V	Q
2	25	50	2	1.59	.1414	9.49	474
5	25	125	5	2.92		17.5	2183
8	25	200	8	3.99		23.9	4777
10	25	250	10	4.63		27.7	6928
20	125	1300	10.4	4.76		28.5	37034
30	150	2550	17.0	6.60		39.5	100,630




D-7

**STORCH ENGINEERS**  
Engineers - Landscape Architects  
Planners - Environmental Consultants


JOB 41-163  
SHEET NO. 8 OF 9  
CALCULATED BY KSP DATE 7/3/80  
CHECKED BY BDC DATE 5/15/80  
SCALE SECTION III

800 → 1800 'Down stream



10  
25  
slope = 5%  
n = .05

D	WP	A	R	$R^{2/3}$	$S^{1/2}$	V	Q
2'	30	50	1.66	1.405	.2236	9.30	280
5	50	125	3.50	2.303		15.24	2667
8	110	418	3.77	2.421		16.02	6650
10	150	675	4.50	2.725		18.04	12176
20	230	2290					



# STORCH ENGINEERS/STORCH ASSOCIATES

Engineers - Landscape Architects  
Planners - Environmental Consultants

JOB 44/63

SHEET NO. 9

OF 9


CALCULATED BY KJP

DATE 7/3/80

CHECKED BY BDC

DATE 7/15/80


SCALE Section IV



$n = .05$

$S = 1.25\%$

D	KA	A	R	$R^{2/3}$	$S^{1/2}$	V	Q
2	65	115	1.77	1.46	0.11	4.77	549
5	93	358	3.85	2.46	0.11	8.04	2879
8	120	680	5.67	3.18	0.11	10.39	7069
10	140	950	6.79	3.58	0.11	11.70	11119
20	230	2800	12.17	5.29	0.11	17.29	48423
30	325	5625	17.3	6.69	0.11	21.87	123074





APPENDIX E

INFORMATION AS CONTAINED IN  
THE NATIONAL INVENTORY OF DAMS